

ENGINEERING REPORT

NCH Healthcare Northeast-Temporary Office

SECTION 23, TOWNSHIP 48 S, RANGE 26 E Collier County, Florida

PREPARED FOR:

NCH Healthcare System, Inc. 350 7th Street North Naples, Florida

PREPARED BY:

Davidson Engineering, Inc. 4365 Radio Road, Suite 201 Naples, Florida 34104

Ryan A. White, P.E., Registration No. 67400 Company ID No. 9496

October 30, 2014

TABLE OF CONTENTS

Existing Condi	itions	. 2
Plan of Consti	ruction	. 2
	r Supply	
General Us	e & Irrigation	. 3
	tion	
Sanitary Sewe	er	. 3
Storm Water	Management	. 4
Appendix A:	Potable Meter Sizing Worksheet	
Appendix B:	NFPA Required Fire Flow Worksheet	
Appendix C:	North Naples Fire District Hydrant Flow Results	
Appendix D:	Collier County Lift Station No. 167.00 – Record Drawings	

Tract 3 - Existing/Conceptually Permitted versus Proposed Dry Detention Areas Exhibit

Appendix E: Cameron Commons Unit 1 Phased Storm Water Management Plan

Appendix F:

General

NCH Healthcare Northeast- Temporary Office (NCH) is a 1.01± acre parcel in the commercial plat of Cameron Commons Unit 1 within Heritage Bay PUD (Original Ordinance #03-40, revised Ordinance #10-24). The project is located in Section 23, Township 48 South, and Range 26 East of Collier County, Florida. It is bounded by Cameron Commons Unit 1 development on the north, east, and west sides and Immokalee Canal on the south with Immokalee Road right-of-way beyond.



Existing Conditions

The NCH property is also known as "Tract 3" under Cameron Commons Unit 1. It was cleared under PPL-AR-5877 and currently exists as vacant land. Also during under the approved PPL water management, underground utilities and a shared internal roadway with easements were constructed. Utilities on NCH site include one hydrant, 4-inch potable watermain stub out, and 6-inch sanitary stub out for connection. The property features access from C.R. 951 Extension and Bellaire Bay Drive.

Plan of Construction

The project proposes a temporary one-story modular building for medical office use. It is 3,480 square feet (SF) and will be constructed with associated parking, connection to existing underground utilities, and landscaping as required by Collier County land development code in phase one of the project. The future phase two portions will include an inter-connect driveway with the adjacent CVS site to the west and a permanent dumpster enclosure with masonry walls. An amendment to the SDP and an additional

modification to the SFWMD ERP will be required for the future phase two site improvements. This parcel was previously permitted with South Florida Water Management District (SFWMD) under modified permit #11-02234-P-05 and will provide storm water management accordingly.

The infrastructure construction will commence upon Collier County and SFWMD approval. A construction schedule will be provided to all interested parties prior to or at the time of preconstruction meeting.

Potable Water Supply

General Use & Irrigation

Potable water and irrigation will be provided by Collier County Utilities via the existing 4-inch watermain stubbed out for development during original PPL construction. The service line extends from the 4-inch main approximately 20 feet to the property line where stub-out is located. NCH proposes connection with a 2-inch line that will provide service for the proposed use. An existing potable master meter located in the southeast corner of Tract 5 was previously sized to accommodate all flows from Cameron Commons Unit 1. Appendix A offers the potable meter sizing worksheet for NCH.

Fire Protection

Water for fire protection will be provided by Collier County Utilities via the existing hydrant located on site. This hydrant was also constructed during the PPL phase of development and provides adequate flow for the proposed temporary non-sprinkled building. Using the NFPA fire flow table, the required fire flow for the proposed building type is as follows (see Appendix B for full table):

Construction IBC Type: V-B (Temporary Modular Trailer)

Building Fire Area: 3,480 SF Required Fire Flow: 1,500 GPM

Based on the hydrant test conducted by North Naples Fire District, provided in Appendix C, the overall hydrant system will provide adequate water supply to exceed the required minimum flow throughout the site.

Sanitary Sewer

General

Sanitary service will be provided by Collier County Utilities. The project proposes connection to the existing 6-inch PVC lateral located on the north property line. This existing stub-out connects to Cameron Commons Unit 1's gravity system which has ultimate discharge into the existing County lift station (No. 167.00) on the southeast corner of Bellaire Bay Drive and the shared internal access. This County station was designed to accommodate all wastewater flows (up to 20,000 sf commercial use plus 210 residential units) from the Cameron Commons Unit 1 commercial development. The lift station record drawings are provided in Appendix D. These flows were originally based on the Florida Building

Code and F.A.C. 64E-6. The following calculations have been utilized for sizing this project's sewer infrastructure; see Table 1 – Proposed Sewer Demands.

Table 1: Proposed Level of Service Demand

Description	Unit Type	GPD/Unit	# Units ¹	Average Daily Demand, GPD	Peak ² Daily Demand, GPM
Doctor/Dentist	Practitioner	250	3	750	2.08
Office	Employee/8 hour shift	15	6	90	0.25
			Total:	590	2.33

Based on FAC: 64E.6.008 System Size Determination

Storm Water Management

The proposed project was previously permitted under modification number 11-02234-P-05 known as Cameron Commons Unit 1. This entire commercial development was permitted as a phased project within Basin 8 of Heritage Bay PUD under master permit 11-02234-P. Table 2, below, summarizes the design criteria for Basin 8.

Table 2: Cameron Commons Unit 1 – Basin 8 Design Criteria

	Ft-NGVD	Ft-NAVD
Control Elevation	12.80	11.55
10-year, 1-day Storm Stage	14.60	13.35
25-year, 3-day Storm Stage	15.40	14.15
100-year, 3-day Storm Stage	16.50	15.25
Minimum Parking Lot Elevation	14.90	13.65
Minimum Road Crown /Perimeter Berm Elevation	15.60	14.35
Minimum Finish Floor Elevation	17.10	15.85

Datum Conversion- NAVD + 1.25 = NGVD

The required 1/2-inch dry pretreatment volume for Cameron Commons Unit 1 is 0.507 ac-ft. The entire phased project conceptually proposed a series of interconnected dry detention areas capable of storing 0.63 ac-ft of storm water. Please refer to Appendix E for the approved phased drainage plan.

NCH (Tract 3) is proposing to sheet flow all runoff into the on-site dry detention area for storm water conveyance to the existing control structure located in northeast corner of Cameron Commons Unit 1. The required pretreatment volume for NCH tract 3 is 0.042 ac-ft. The previous conceptually permitted volume was 0.05 ac-ft. Currently proposed on site is 0.087 ac-ft. (See Appendix F for existing/conceptually permitted versus proposed dry detention areas.)

¹Conservatively calculated by assuming 1 practitioner per 2,000 sf and 3 employees per practitioner.

²Peak factor of 4.5 as calculated per Figure 1 – Ratio of Peak Hourly Flow to Design Average Flow, "Recommended Standards for Wastewater Faculties," 1997 Ed., Great Lakes – Upper Mississippi River Board of State and Provincial Public Health and Environmental Managers.

APPENDIX A

Potable Meter Sizing Worksheet



Water Meter Sizing Form

One Form Per Meter

Please call Public Utilities Engineering (239) 252-2583 with any questions.

Preparer's Information:		Project Information:	Date ====>	28-	-Oct-14
Name ======>	Josh Fruth	Permit or AR Number			
Title ======>	Project Manager	Name of Project ===>	NCH Healthcare Northe	ast - Temporar	y Office
Company=====>	Davidson Engineering	Project Address ===>	T.B.	D.	
Address ======>	4365 Radio Road				
	Naples, Florida 34104				
Phone ======>	239-434-6060				
Email Address ====>	josh@davidsonengineering.com				
metered residential devel	s must be metered separately from residential faci opment and designed for the exclusive use of the	residents within such development.			proceure loss
of 5.5 psi.	e service shall be selected to allow a maximum pre	essure loss at design flow of 5 psi exce	ept the 3-inch meter shall be	a maximum	pressure loss
3. Additional fees may ap	oply if a backflow device is deemed necessary by t	he Water Distribution Department.			
Fixture Flow Values as sh	Architect must submit signed and sealed documen nown on the following page and sized as per the Tars rs the Engineer/Architect must consider all relevan	able on page 3 unless approved other	wise by the Collier County U		
5. For remodeling project	cts this form must be submitted only if there is a ne	t increase in Fixture Flow Value.			
	This Section to be filled	out by Engineer/Architect of I	Record:		
	e with the Fixture Flow Value Worksheet able for Estimating Demand	25.85 GPM	Demand Range (GPM)	Meter Size	
(Engineer/Architect must at	tach a completed Fixture Flow Value Worksheet)		0 to 24	3/4"	
			24.1 to 40	1"	
N	Meter Size in Inches	Connecting to Master Meter	40.1 to 80	1 1/2"	
	g, Engineer/Architect must identify the meter facturer and model number)		80.1 to 144	2"	
			144.1 to 405	3"	
			405.1 to 900	4"	
Type or Print Name of Engin	neer/Architect of Record for Project				
Signature of Engineer/Archi [Affix Engineering/Architect	tect of Record for Project and Date Stamp Here]				



Fixture Flow Value Worksheet

Supporting Documentation

Please call Public Utilities Engineering (239) 252-2583 with any questions.

Enter # of Fixtures of each Fixture Type, per unit, then multiply by appropriate Flow Rate to get Fixture Value

Fixture)			Flow Rate		# of Fixtures Per Unit	Fixtur	e Flow Value
Automatic clothes Wash	ner							
Commercial				3	X		=	
Residential				2	Х		=	
Bathroom group								
As defined in FL Plu		on 202						
	water closet)			5	X		=	
As defined in FL Plu (water closet flushi				6				
Bathtub	ng greater than 1.	o gpi)		4	X		_	
Bidet				2	x		_	
Dental unit or cuspidor				1	······································		_	
Dishwasher, residential				2.75	······································		_	
Drinking fountain				0.75	······································		_	
Shower				3	X		_	
Sillcock, hose bibb				5	X		_	
Sink (per faucet)							=	
Kitchen, residential				2	······································	1	_	2
Laundry tray				4			=	<u>Z</u>
Lavatory				2	X	A	_	8
Service				3	x	1	_	3
Wash				2	x	9	_	<u>3</u> 18
Urinal								
Standard				4	~		_	
Flushless				0	X		_	
Valve*	Gallons/Flush =	0.16	x10	1.6	······································		_	
Water Closet	Gallotis/Flusit =	0.10	<u> </u>	1.0			=	
Flushometer valve*	Gallons/Flush =		x10		······································		_	
Flushometer tank	Gallotis/Flusit =		A I U	1.6	X	4	_	6.4
Tank				4	X	***************************************	_	0.4
For any fixtures not liste	od submit manufe	eturor'e do	ta choot		x	on and value:	=	
Other: ICE MAKER	u, subiliii ilidilula	iciuiei 5 Ud	ia Sileel	s and enter approp		on and value.		1
Other:				I	X	I		I
Other:					X			
Other:					X			
Other:					X			
Outer.					Х	Total Fixture Value Pe	= er Unit =	38.4
	ŀ				Number	of Units with this Fixture		1
	F		Grand T	otal of Fixture FI		Unit Total x Number of U		38.4
		(rand I	otai ot Fixture Fi	ow value (Per	Unit Total X Number of U	nits)^^ ====>	38.4

^{*}Valves are calculated using a flush rate of 10 flushes per minute (according to Florida Plumbing Code). The flow rate is 10 times the gallons per flush.

The fixture flow value is calculated as follows:

Number of Valves Calculation

Flow Rate times Number of Fixtures. 1 - 2 3 - 10

Flow Rate ${\it times}$ two ${\it plus}$ two ${\it times}$ the Number of Fixtures. 11 or more Flow Rate times Number of Fixtures divided by two.

^{**}Use total Fixture Flow Value on "Table for Estimating Demand" to estimate water meter demand.



Table for Estimating Demand

Supporting Documentation

Please call Public Utilities Engineering (239) 252-2583 with any questions.

	INANTLY FOR FLUSH TANKS	SUPPLY SYSTEMS PREDOMINANTLY FOR FLUSI VALVES			
Load	Demand	Load	Demand		
Fixture Flow Value	Gallons per minute	Fixture Flow Value	Gallons per minute		
1	3.0				
2	5.0				
3	6.5				
4	8.0				
5	9.4	5	15.0		
6	10.7	6	17.4		
7	11.8	7	19.8		
8	12.8	8	22.2		
9	13.7	9	24.6		
10	14.6	10	27.0		
11	15.4	11	27.8		
12	16.0	12	28.6		
13	16.5	13	29.4		
14	17.0	14	30.2		
15	17.5	15	31.0		
16	18.0	16	31.8		
17	18.4	17	32.6		
18	18.8	18	33.4		
19	19.2	19	34.2		
20	19.6	20	35.0		
25	21.5	25	38.0		
30	23.3	30	42.0		
35	24.9	35	44.0		
40	26.3	40	46.0		
45	27.7	45	48.0		
50	29.1	50	50.0		
60	32.0	60	54.0		
70	35.0	70	58.0		
80	38.0	80	61.2		
90	41.0	90	64.3		
100	43.5	100	67.5		
120	48.0	120	73.0		
140	52.5	140	77.0		
160	57.0	160	81.0		
180	61.0	180	85.5		
200	65.0	200	90.0		
225	70.0	225	95.5		
250	75.0	250	101.0		
275	80.0	275	104.5		
300	85.0	300	108.0		
400	105.0	400	127.0		
500 750	124.0 170.0	500 750	143.0 177.0		
	208.0		208.0		
1,000 1,250	239.0	1,000 1,250	239.0		
			239.0		
1,500	269.0	1,500			
1,750	297.0	1,750	297.0		
2,000	325.0	2,000	325.0		
2,500	380.0	2,500	380.0		
3,000	433.0	3,000	433.0		
4,000	535.0	4,000	535.0		
5,000	593.0	5,000	593.0		

APPENDIX B

NFPA Require Fire Flow Worksheet

CROSS-REFERENCE OF BUILDING CONSTRUCTION TYPES

NFPA 220	I(442)	I(332)	II(222)	II(111)	II(000)	III(211)	III(200)	IV(2HH)	V(111)	V(000)
IBC		IA	IB	IIA	IIB	IIIA	IIIB	IVHT	VA	VB

Table H.5.1 Minimum Required Fire Flow and Flow Duration for Buildings

	Fire A		771			
$^{\mathrm{I}(443),\mathrm{I}(332),}_{\mathrm{II}(222)^{1}}$	$\Pi(111), \\ \Pi I(211)^1$	IV(2HH), V(111) ¹	П(000),Ш(200), ПІ(000) ¹	$V(000)^{1}$	Fire Flow gpm ² (× 3.785 for L/min)	Flow Duration (hours)
0-22,700	0-12,700	0-8,200	0-5,900	0-3,600	1,500	
22,701-30,200	12,701-17,000	8,201-10,900	5,901-7,900	3,601-4,800	1,750	
30,201-38,700	17,001-21,800	10,901-12,900	7,901-9,800	4,801-6,200	2,000	
38,701-48,300	21,801-24,200	12,901-17,400	9,801–12,600	6,201-7,700	2,250	2
48,301-59,000	24,201-33,200	17,401-21,300	12,601-15,400	7,701-9,400	2,500	
59,001-70,900	33,201-39,700	21,301-25,500	15,401-18,400	9,401–11,300	2,750	
70,901–83,700	39,701-47,100	25,501-30,100	18,401-21,800	11,301-13,400	3,000	
83,701-97,700	47,101-54,900	30,101-35,200	21,801-25,900	13,401-15,600	3,250	
97,701-112,700	54,901-63,400	35,201-40,600	25,901-29,300	15,601-18,000	3,500	3
112,701–128,700	63,401-72,400	40,601-46,400	29,301-33,500	18,001-20,600	3,750	
128,701-145,900	72,401-82,100	46,401-52,500	33,501-37,900	20,601-23,300	4,000	
145,901-164,200	82,101-92,400	52,501-59,100	37,901-42,700	23,301-26,300	4,250	
164,201-183,400	92,401-103,100	59,101-66,000	42,701-47,700	26,301-29,300	4,500	
183,401-203,700	103,101-114,600	66,001-73,300	47,701–53,000	29,301-32,600	4,750	
203,701-225,200	114,601-126,700	73,301-81,100	53,001-58,600	32,601-36,000	5,000	
225,201-247,700	126,701-139,400	81,101-89,200	58,601-65,400	36,001-39,600	5,250	
247,701–271,200	139,401-152,600	89,201-97,700	65,401-70,600	39,601-43,400	5,500	
271,201–295,900	152,601-166,500	97,701–106,500	70,601-77,000	43,401-47,400	5,750	
295,901–Greater	166,501–Greater	106,501-115,800	77,001-83,700	47,401-51,500	6,000	4
295,901–Greater	166,501–Greater	115,801-125,500	83,701-90,600	51,501-55,700	6,250	
295,901–Greater	166,501–Greater	125,501-135,500	90,601-97,900	55,701-60,200	6,500	
295,901–Greater	166,501–Greater	135,501-145,800	97,901–106,800	60,201-64,800	6,750	
295,901–Greater	166,501–Greater	145,801-156,700	106,801-113,200	64,801-69,600	7,000	
295,901–Greater	166,501–Greater	156,701–167,900	113,201-121,300	69,601-74,600	7,250	
295,901–Greater	166,501–Greater	167,901-179,400	121,301-129,600	74,601–79,800	7,500	
295,901–Greater	166,501–Greater	179,401–191,400	129,601-138,300	79,801–85,100	7,750	
295,901–Greater	166,501–Greater	191,401–Greater	128,301–Greater	85,101–Greater	8,000	

 $^{^{1}}$ Types of construction are based on NFPA 220. 2 Measured at 20 psi (139.9 kPa).

APPENDIX C

North Naples Fire District Hydrant Flow Results

James Burke, Chairman Norman E. Feder, Vice Chairman Margaret Hanson, Treasurer John McGowan, Commissioner J. Christopher Lombardo, Commissioner



Fire Prevention Bureau 6495 Taylor Road Naples, FL 34109 239-597-9227 Phone 239-597-3522 Fax

North Naples Fire Control and Rescue District

June 9, 2014

Ms. Jessica Harrelson Davidson Engineering 4365 Radio Road #201 Naples, FL 34104

Fax: 239-434-6084

Re:

Flow Test @ Heritage Bay Commons - Bellaire Bay Drive

(Flow Hydrant #55-68-042 - Static Residual #68-041)

The North Naples Fire Control and Rescue District has conducted a flow test at the above location. This also will serve as an invoice in the amount of \$100.00 to cover the cost of the test. (#10827).

Please make your check payable to North Naples Fire District and please reference the name of the project on your check.

Following are the results of the flow test:

Static:

77

Residual:

54

Total Flow GPM:

2,276

Pitot:

46 x 2 Ports

Flow @ 20 PSI GPM:

3,716

Time:

10:30 AM - 6-6-14

If you have any questions, please do not hesitate to contact me @ (239) 597-9227.

Sincerely,


Don Baer, Battalion Commander Fire Prevention

North Naples Fire District

DB:ds


APPENDIX D

Collier County Lift Station No. 167.00 – Record Drawings



APPENDIX E

Cameron Commons Unit 1 Phased Storm Water Management Plan



APPENDIX F

Tract 3 – Existing/Conceptually Permitted

Versus Proposed Dry Detention Areas

